

Bruhath Bangalore Mahanagara Palike

Office of the Executive Engineer
Electrical Division, Yelahanka Zone
Bruhath Bengaluru Mahanagara Palike

"Schedule-B"

Name of the Work:-Repairs to Borewell and Water Pump at Medi Agrahara Crematoria Lakshmipura in ward No-11						
Sl. No.	Approved Qty	Description	Unit	Approved Rates		Amount
				in Figures	In Words	
1	1	Supplying and Fixing of Submersible Single Phase Atalanta/Suguna/CRI/Kirloskar/Other Equivalent Pumps 1.5 H.P/ 1.1 K.W KPWD CIVIL SR -2014-15 P.No-XXXXIV	Each	15700.00	Rupees Fifteen Thousand and Seven Hundred Only	15700.00
2	1	Supplying fully automatic star-delta starter unit push button type with suitable wires, 3 contactors, one adjustable thermal timer mounted on a common base plate held in steel enclosure for use on 400/440 volts 3 phase and wired after fixing to the existing wooden board for motor. 6.2.2) Above 15 HP upto 25 HP	Each	8273.00	Rupees Eight Thousand Two Hundred and Seventy Three Only	8273.00
3	1	6.3) Supplying and fixing single phase preventer using necessary wires over an existing panel board suitable for motor up to 20 HP capacities	Each	768.00	Rupees Seven Hundred and Sixty Eight Only	768.00
4	1	Supplying push button operated direct online starter with an antiweld silver cadmium oxide contactor with replaceable fixed and moving contacts and bimetallic thermal overload relay help in anticorrosion treated sheet steel or iron clad enclosure and fixing the same to suitable capacity wires for 400/440 volts 3 phase motor/single phase motor upto 5 HP.	Each	1427.00	Rupees One Thousand Four Hundred and Twenty Seven Only	1427.00
5	75	Supplying and drawing 3 core flat PVC sheathed submersible pump cable manufactured with electrolytic grade copper with flexible copper with low resistance conductor confirming to table 3 class 5 of IS:8130-1984 and virgin grade PVC insulation and powder coating extruded PVC sheathed suitable for working voltage upto 1100Volts as per IS-694:1990 & confirming to GTP of GROUP-A 2.10.2) 3C X 2.5Sq.mm	mtr	86.30	Rupees Eighty Six and Thirty Paise Only	6472.50
6	150	KSRB 13-9.1:- Providing and fixing to wall , ceiling and floor high density polyethylene pipes 6.00 kgf/sq.cm working pressure 32 mm outside diameter with special flange, compression type fittings, wall clips, making good the wall, ceiling and floor, including cost of all materials, labour charges, HOM of equipments and testing complete as per specifications. Specification No.KBS 13.2.15.2/13.9 Page No.102 Sl no:-13.71 (Area weightage 6 % to be added) Basic rate Rs 228.00/m i.e Rs.241.7	mtr	241.70	Rupees Two Hundred Forty One and Seventy Paise Only	36255.00

7	6	Gate Valve 32 mm Nominal bore-gun metal Page No.XXIV SI no:-671(Area weightage 6 % to be added) Basic rate Rs 750.00/each i.e Rs.795.00	Each	795.00	Rupees Seven Hundred and Ninty Five Only	4770.00
8	5	Gate Valve 15 mm Nominal bore-gun metal Page No.XXIV SI no:-668(Area weightage 6 % to be added) Basic rate Rs 250.00/each i.e Rs.265.00	Each	265.00	Rupees Two Hundred and Sixty Five Only	1325.00
Total Amount						74990.50

I am prepared to take up the above work rates quoted in the Schedule 'B'

For CHOWDESHWARI ELECTRICALS

 CONTRACTOR
 Proprietor


 EXECUTIVE ENGINEER (Ele)
 YELAHANKA ZONE, BBMP